



Do you already know the specifications of our **CLIMATE HALL** in Mudau-Germany?

In this test facility we are able to test HVAC systems to the limit, including noise, lifetime, through to efficiency.

This climate hall is best suited to validate the functionality of heating cooling systems prior to the series productions.

Our highly qualified team and test facility are available to support you for tests of either entire systems, or even individual components.




OVERVIEW AURORA CLIMATE HALL MUDAU

TEST VARIANTS AND TECHNICAL INFORMATION

Technical Data	Climate hall AURORA DE-Mudau
Cooling	Down to -10°C / 14°F (standard)
	Down to -46°C / -50.8°F (special measurement)
Heating	Up to 50°C / 122°F
Moisturization	Up to 70% relative humidity
Solar simulation	IR emitter Performance < 1500W/m ²
Length of vehicle	< 15.0 m
Height of vehicle	< 4.0 m
Width of vehicle	< 3.5 m

- The climate hall is suitable for all kinds of vehicles and cabs
- Centralized data logging: temperature, humidity, pressure
- Control of climate hall temperature, solar simulation
- Monitoring of the ongoing climate hall tests via heatable inspection window

For an individual quotation please contact AURORA!



leon.hoege@aurora-eos.com
Phone: +49 6284 9202-1105

Phone: +49 6284 9202-1105

